



Associated British Ports South Wales

NOTICE TO MARINERS.

NO 10 OF 2023

Cardiff Valero Berth Works Date Extension

Mariners, Shipping agents and Customers are advised that due to refurbishment work on the Valero Jetty, Cardiff Roath Dock, the dock level will be reduced in Cardiff to 11.0m on the following dates:

March 6th 2023
March 13th – 17th 2023
March 27th – 31st 2023
April 3rd – 4th 2023
April 11th – 14th 2023
April 17th 2023
April 24th – 28th 2023
May 1st – 4th 2023
May 10th – 12th 2023
May 16th – 16th 2023
May 22nd – 26th 2023
May 29th – 2nd June 2023
June 8th – 1st July 2023
July 9th – 31st 2023

Below is a revised Cardiff Dock acceptance table which should be referenced for these dates. Outside of these dates the dock level will be maintained at the normal 11.8m – 12.0m level.

HARBOUR MASTER SOUTH WALES
Queen Alexandra House, Cargo Road, CARDIFF, CF10 4LY

Date 14/03/2023.

All ABP South Wales Notices to Mariners may be viewed on: - www.southwalesports.co.uk
Owners, Agents and Charters should ensure that the contents of this notice are made known to the masters or persons in charge of their vessel or craft.

Acceptance Table - Cardiff Docks - Valero Works period March - June 2023

For a dock level of 11.0 metres			
	Vessels may be accepted by Cardiff LPS up to the draft indicated without referral to the Harbour Master.	Vessels may be accepted by Cardiff LPS up to the beam indicated without referral to the Harbour Master	Vessels may be accepted by Cardiff LPS up to the length indicated without referral to the Harbour Master
Queen Alexandra Lock			
QA Lock	Refer to Berth	25 m	185 m
Queen Alexandra Dock			
West End Cross Berth	6.1m	25 m	150 m
No. 1 Berth	6.1m	25 m	185 m
No. 2 Berth	7.3m		
A Shed	7.3m		
D Shed	7.4m		
F Shed	7.5m		
Bells Wharf	8.9m		
Empire Wharf	4.1m	15 m	150 m
Kings Wharf	7.8m	25 m	150 m
Coastal	8.7m	25 m	185 m
Seawood Shed/ I Shed	8.2m		
Oil Berth 1	8.1m		
Communication Passageway	9.0m	25 m	160 m
Roath Dock			
Pontoon Berth	7.5m	25 m	160 m
Hanson	5.9m		
EMR	8.7m		
Valero	8.7m		
Ryans Wharf	8.7m		
H Shed	8.7m		
Roath Basin			
Britannia Quay	7.9m	22	140
Dock Level	The dock level can not be guaranteed but will generally be held at the average of 11.75 m		
Dock Water Density	Q A Dock	1006	
	Roath Dock	1006	
	Roath Basin	1006	
Stemming Allowance in the Wrach Channel	Please refer to latest Notice to Master for present Allowance		
Specific berth acceptance draft is at all times subject to the predicted tide height and the application of the advertised stemming allowance			